# PG&E's NAS Battery Demonstration Projects

December 1, 2014



Jon Eric Thalman

Robert Schainker FPRI



## **PG&E's Battery Energy Storage Systems**



Vaca-Dixon BESS
2 MW / 14 MWh NAS Battery
Vaca-Dixon Substation

#### **Accomplishments**

- Peak shaving
- CAISO NGR Energy & Ancillary
  Services
- Renewable Integration

#### **Current Operation**

 Focused on optimizing for and quantifying revenues from participation in energy and ancillary services markets.



Yerba Buena BESS 4 MW / 28 MWh NAS Battery Customer R&D Facility, San Jose

#### **Accomplishments**

- Peak shaving
- Power Quality
- Islanding

#### **Current Operation**

- Capacity and power quality
- Islanding backup for the adjacent customer facility.




## Operational Efficiency Summary

#### **Lessons-Learned**

- 1. The NaS Battery Energy Storage System (BESS) Achieved Very Close To The Manufacturer Performance Levels For Max Power Level, Max Discharge Time, and **Max Energy Level** 
  - a) Utility Side of the Meter: 2 MW, 7 Hours, 14MW-Hours
  - b) Customer Side of the Meter: 4 MW, 7 Hours, 28 MW-Hours
- 2. The AC Efficiency During Back-to-Back Charge And Discharge Time Periods Remains Relatively Constant At 80% For A Wide Variety Of Discharge Levels. Note: The Overall Effective 24 Hour AC Efficiency Metric Is Highly Dependent On The Length Of The Battery System Idle Time, The Battery Heater Energy Used, The Heater Control System, And The Time Interval Over Which The AC Efficiency Metric Is Calculated.
- 3. AC Efficiency Improves As Discharge Time Increases. This Is Especially Useful For Relieving T&D system Equipment During Grid Peak Load Time Periods (e.g., From 12 Noon To 6 PM).
- 4. Power Quality IEEE Standard Levels (Current Harmonics and Voltage Flicker) Were Met (e.g., IEEE 1547).
- 5. The BESS Operated Successfully For Applications That Encompassed Power Smoothing, Frequency Regulation, Peak Shaving, VAR Control, And Ramping Duty Cycles.




## 4 MW Plant Efficiency At 6 Hr Discharge Vs. Load






## 2 MW Plant Efficiency Vs. Discharge Time





## Distribution Support: Renewable Smoothing

### Demonstrated ability of BESS to smooth output from 2 MW solar array



Note: Historical solar output from 2MW Vaca-Dixon **Solar Facility** used here, as system does not have connected PV system



## **Distribution Support: Islanding**

Yerba Buena system response to zero voltage condition on feeder. Restored service in less than 4 cycles.





Table 2. Time Each Phase is Below 90% RMS Voltage During Figure 12.

| 111010 27 111110 211101 1 111100 10 2010 17 7 0 7 0 111110 |                 |           | , eringe is ming right til. |        |
|--|-----------------|-----------|-----------------------------|--------|
|  | RMS Voltage (V) | Time (s)  | Delta time (s)              | Cycles |
| A Phase  | 10894.99        | 0.0520200 | 0.05352                     | 3.2112 |
|  | 10925.98        | 0.1055400 |                             |        |
|  |                 |           |                             |        |
| B Phase  | 10911.28        | 0.0498600 | 0.05396                     | 3.2376 |
|  | 10914.81        | 0.1038200 |                             |        |
|  |                 |           |                             |        |
| C Phase  | 10899.87        | 0.0487200 | 0.05906                     | 3.5436 |
|  | 10918.98        | 0.1077800 |                             |        |

## Market Participation: Ancillary Services (Frequency Regulation) Testing

#### Response of Vaca BESS to CAISO 4-second AGC signal




Nearly instantaneous response creates potential for extra Pay-For-Performance and Flexible Ramping revenues, although value is unknown at this time.

Date: 9/26/14

Award: +1.9 MW Reg Up

-2.1 MW Reg Down

**Duration: 6 continuous hours, 11 AM to 5 PM** 



- Our experience with the NAS Battery Energy Storage System pilot projects is proving that the technology works and meets manufacturer specifications
- Parasitic and efficiency losses have significant impact on operational costs and constrain use cases
- Have experienced higher than expected failure of power conversion system components
- We are now beginning an earnest exploration of optimizing these resources for CAISO markets, and deploying necessary automation technology to take full advantage of fast-response capabilities of these resources