Palmdale Hybrid Power PROJECT

APPLICATION FOR CERTIFICATION

Volume 1

Submitted on Behalf of:

PALMDALE
a place to call home

Submitted by:

Inland Energy, Inc.

Submitted to:

California Energy Commission

July 2008

Prepared by:

ENSR | AECOM

Submitted to:
California Energy Commission

Palmdale Hybrid Power Project
Application For Certification

Volume 1

Submitted on Behalf of:
City of Palmdale

By:
Inland Energy, Inc.

Prepared by:
ENSR Corporation

July 2008

Volume 1 Contents

1.0 Executive Summary 1-1

1.1 Project Overview 1-1

1.2 Project Location and Description 1-2

1.3 Project Alternatives 1-3

1.4 Environmental Information 1-3

1.4.1 Air Quality 1-3
1.4.2 Biological Resources 1-4
1.4.3 Cultural Resources 1-5
1.4.4 Geologic Resources and Hazards 1-5
1.4.5 Hazardous Materials Handling 1-5
1.4.6 Land Use 1-5
1.4.7 Noise 1-6
1.4.8 Paleontological Resources 1-6
1.4.9 Public Health 1-6
1.4.10 Socioeconomics 1-6
1.4.11 Soils 1-7
1.4.12 Traffic and Transportation 1-7
1.4.13 Transmission System Safety and Nuisance 1-7
1.4.14 Visual Resources 1-7
1.4.15 Waste Management 1-8
1.4.16 Water Resources 1-8
1.4.17 Worker Safety 1-8

2.0 Project Description 2-1

2.1 Introduction and Overview 2-1

2.2 Location of Facilities 2-3

2.3 Site Description 2-3

2.3.1 Existing Site Condition 2-3

2.4 Generating Facility Description 2-4

2.4.1 Site Arrangement 2-4
2.4.2 Process Description 2-5
2.4.3 Energy Conversion Facilities Description 2-8

2.4.4 Electrical System Description 2-13
2.4.5 Plant Auxiliary Systems and Process Descriptions 2-17
2.4.6 Project Civil/Structural Features 2-27
2.4.7 Pipeline Facilities Description 2-30
2.4.8 Project Construction 2-31
2.5 Transmission System Description 2-32
2.5.1 Transmission Line Construction 2-33

3.0 Closure 3-1

3.1 Temporary Closure 3-1

3.2 Permanent Closure 3-1

4.0 Project Alternatives 4-1

4.1 No Project Alternative 4-1

4.2 Project Site Alternatives 4-2
4.2.1 Alternative Power Generation Sites 4-3
4.2.2 Linear Facilities Route Alternatives 4-4

4.3 Power Generation Facility Design Alternatives 4-5
4.3.1 Cooling Technology Alternatives 4-5
4.3.2 Wastewater Disposal Alternatives 4-10
4.3.3 Cooling Water Supply Alternatives 4-11

4.4 Power Generation Technology Alternatives 4-11
4.4.1 Conventional Simple Cycle 4-12
4.4.2 Combined-Cycle with and without Solar 4-12
4.4.3 Advanced Combustion Turbine Cycles and Combustion Turbine Equipment 4-13
4.4.4 Integrated Gasification Combined Cycle (IGCC) 4-13
4.4.5 Coal or Other Solid Fuel Conventional Furnace/Boiler - Steam Turbine 4-14
4.4.6 Fluidized Bed Combustion 4-14
4.4.7 Nuclear 4-14
4.4.8 Other Renewable Technologies 4-14

4.5 References 4-14

5.0 Environmental Information 5.1-1

5.1 General 5.1-1
5.1.1 Projects Considered in Cumulative Impact Analysis 5.1-2
5.1.2 References 5.1-3

5.2 Air Quality 5.2-1
5.2.1 LORS Compliance 5.2-1
5.2.2 Affected Environment 5.2-18
5.2.3 Control Technology Assessment 5.2-29
5.2.4 Environmental Impacts 5.2-44
5.2.5 Mitigation Measures 5.2-76
5.2.6 References 5.2-83

5.3 Biological Resources 5.3-1
5.3.1 LORS Compliance 5.3-1
5.3.2 Affected Environment 5.3-7
5.3.3 Environmental Impacts 5.3-37
5.3.4 Mitigation Measures 5.3-50
5.3.5 References 5.3-55

5.4 Cultural Resources 5.4-1
5.4.1 LORS Compliance 5.4-1
5.4.2 Affected Environment 5.4-7
5.4.3 Environmental Impacts 5.4-33
5.4.4 Mitigation Measures 5.4-37
5.4.5 References 5.4-38

5.5 Geologic Hazards and Resources 5.5-1
5.5.1 LORS Compliance 5.5-1
5.5.2 Affected Environment 5.5-2
5.5.3 Environmental Impacts 5.5-9
5.5.4 Mitigation Measures 5.5-10
5.5.5 References 5.5-11

5.6 Hazardous Material Handling 5.6-1
5.6.1 LORS Compliance 5.6-1
5.6.2 Affected Environment 5.6-9
5.6.3 Environmental Impacts 5.6-10
5.6.4 Mitigation Measures 5.6-29
5.6.5 References 5.6-32

5.7 Land Use 5.7-1
5.7.1 LORS Compliance 5.7-1
5.7.2 Affected Environment 5.7-17
5.7.3 Environmental Impacts 5.7-21
5.7.4 Mitigation Measures 5.7-23
5.7.5 References 5.7-24

5.8 Noise 5.8-1
5.8.1 LORS Compliance 5.8-1
5.8.2 Affected Environment 5.8-5
5.8.3 Environmental Impacts 5.8-10
5.8.4 Mitigation Measures 5.8-17
5.8.5 References 5.8-18

5.9 Paleontological Resources 5.9-1
5.9.1 LORS Compliance 5.9-1
5.9.2 Affected Environment 5.9-4
5.9.3 Environmental Impacts 5.9-11
5.9.4 Mitigation Measures 5.9-12
5.9.5 References 5.9-14

5.10 Public Health 5.10-1
5.10.1 LORS Compliance 5.10-1
5.10.2 Affected Environment 5.10-7
5.10.3 Environmental Impacts 5.10-8
5.10.4 Mitigation Measures 5.10-25
5.10.5 References 5.10-25

5.11 Socioeconomics 5.11-1
5.11.1 LORS Compliance 5.11-1
5.11.2 Affected Environment 5.11-3
5.11.3 Environmental Impacts 5.11-17
5.11.4 Mitigation Measures 5.11-34
5.11.5 References 5.11-34

5.12 Soils 5.12-1
5.12.1 LORS Compliance 5.12-1
5.12.2 Affected Environment 5.12-3
5.12.3 Environmental Impacts 5.12-9
5.12.4 Mitigation Measures 5.12-10
5.12.5 References 5.12-11

5.13 Traffic and Transportation 5.13-1
5.13.1 LORS Compliance 5.13-1
5.13.2 Affected Environment 5.13-5
5.13.3 Environmental Consequences 5.13-11
5.13.4 Mitigation Measures 5.13-23
5.13.5 References 5.13-23

5.14 Transmission Line Safety and Nuisance 5.14-1
5.14.1 LORS Compliance 5.14-1
5.14.2 Affected Environment 5.14-4
5.14.3 Impact Analyses 5.14-5
5.14.4 Mitigation Measures 5.14-8
5.14.5 References 5.14-8

5.15 Visual Resources 5.15-1
5.15.1 LORS Compliance 5.15-1
5.15.2 Affected Environment 5.15-4
5.15.3 Environmental Impacts 5.15-8
5.15.4 Mitigation Measures 5.15-16
5.15.5 References 5.15-16

5.16 Waste Management 5.16-1
5.16.1 LORS Compliance 5.16-1
5.16.2 Affected Environment 5.16-8
5.16.3 Environmental Impacts 5.16-10
5.16.4 Mitigation Measures 5.16-16
5.16.5 References 5.16-17

5.17 Water Resources 5.17-1
5.17.1 LORS Compliance 5.17-1
5.17.2 Affected Environment 5.17-7
5.17.3 Environmental Impacts 5.17-11
5.17.4 Mitigation Measures 5.17-14
5.17.5 References 5.17-15

5.18 Worker Safety 5.18-1
5.18.1 LORS Compliance 5.18-1
5.18.2 Affected Environment 5.18-9
5.18.3 Environmental Impacts 5.18-9
5.18.4 Mitigation Measures 5.18-21
5.18.5 References 5.18-21

6.0 List of Contributors 6-1

List of Appendices

Appendix A Surrounding Properties: Assessor's Parcel Nos./Property Owners

Appendix B Preliminary Geotechnical Investigation Report – Kleinfelder

Appendix C Engineering Design Criteria

C.1 Foundations and Civil
C.2 Seismic and Structural
C.3 Mechanical
C.4 Control Systems
C.5 Electrical

Appendix D Therminol™ VP1 Heat Transfer Fluid: Material Safety Data Sheet

Appendix E Agency and Other Correspondence

E.1 County of Los Angeles
– Availability of Adequate Reclaimed Water to Supply the Project
E.2 City of Palmdale – Conditional Will Serve Letter
E.3 California Department of Toxic Substances Control
– Reclassification of Therminol-Contaminated Soil as Non-hazardous waste
E.4 Southern California Logistics Airport – HDPP as No Hazard to Aircraft Operations
E.5 Merrell-Johnson Engineering, Inc. – Obstruction Coordinates for FAA Application

Appendix F System Impact Study (Electrical Interconnection)

Volume 2 Contents

List of Appendices

Appendix G Air Quality Supporting Documentation

G.1 Quarterly Wind Roses
G.2 Control Technology Database
G.3 Construction and Operations Phase Emissions
G.4 Class II Area Dispersion Modeling Protocol
G.5 Class I Area Dispersion Modeling Protocol
G.6 Air Quality - Public Health and Visible Plume - Modeling Files (CD-ROM)
G.7 Public Health Residential, Worker and Sensitive Receptors List

Appendix H Biological Resources Technical Report/Biological Assessment

H.1 Palmdale Hybrid Power Project Biological Technical Report
H.2 Correspondence with Federal and California State Agencies Regarding Palmdale Hybrid Power Project

Appendix I Cultural Resources Technical Report

Appendix J Paleontological Resources Technical Report

Appendix K Phase I Environmental Site Assessment

Appendix L Drainage Erosion Sediment Control Plan

List of Tables

2.0 Project Description

Table 2-1 PHPP Plant Site Parcels- Assessor's Parcel Numbers (APN) 2-4
Table 2-2 Generation Configurations and Output in MW 2-6
Table 2-3 Time (Minutes) to Full Load With and Without GE "Rapid Start Process" 2-9
Table 2-4 Typical Natural Gas Composition 2-17
Table 2-5 Daily and Annual Water Uses 2-18
Table 2-6 Expected Palmdale Water Reclamation Plant Reclaimed Water Quality Data1 2-19
Table 2-7 Combined-Cycle Emission Rates 2-24
Table 2-8 HTF Heater Gas Usage Estimates 2-27

4.0 Project Alternatives

Table 4-1 Net Power Effects and Annual Operating Cost Comparison Wet Cooling v. Dry Cooling at the Palmdale Hybrid Power Project 4-8

5.2 Air Quality

Table 5.2-1 Federal, State and Local LORS Applicable to Air Quality 5.2-2
Table 5.2-2 Agencies and Agency Contacts 5.2-18
Table 5.2-3 Permits Required and Permit Schedule 5.2-18
Table 5.2-4 Temperature Data for Lancaster, California 5.2-21
Table 5.2-5 Precipitation Data for Lancaster, California 5.2-22
Table 5.2-6 National and California Ambient Air Quality Standards 5.2-23
Table 5.2-7 Summary of Attainment Status of the Project Area 5.2-25
Table 5.2-8 Air Quality Monitoring Stations Closest to the Project Site 5.2-25
Table 5.2-9 Ozone Data for Monitoring Stations Closest to the Power Plant Site 5.2-26
Table 5.2-10 PM10 Data for Monitoring Stations Closest to the Power Plant Site 5.2-27
Table 5.2-11 PM2.5 Data for Monitoring Stations Near the Power Plant Site 5.2-27
Table 5.2-12 CO Data for Monitoring Stations Near the Power Plant Site 5.2-28
Table 5.2-13 NO2 Data for Monitoring Stations Near the Power Plant Site 5.2-28
Table 5.2-14 SO2 Data for Monitoring Stations Near the Power Plant Site 5.2-29
Table 5.2-15 Summary of BACT/LAER for the Project 5.2-44
Table 5.2-16 Maximum Daily Combined-Cycle and Solar Array Facility Construction Emissions 5.2-45
Table 5.2-17 Maximum Annual Onsite Combined-Cycle Facility and Solar Array Construction Emissions 5.2-45

Table 5.2-18 Maximum Daily Reclaimed Water, Sanitary Sewer, Natural Gas, Backup Water and Transmission Line Construction Emissions 5.2-45
Table 5.2-19 Estimated Emissions During Commissioning Period 5.2-48
Table 5.2-20 Maximum Annual Emissions from Combustion Turbines 5.2-49
Table 5.2-21 Maximum Hourly Emissions from Two Combustion Turbines 5.2-49
Table 5.2-22 Maximum Hourly and Annual Auxiliary Boiler Emissions 5.2-50
Table 5.2-23 Maximum Hourly and Annual HTF Heater Emissions 5.2-50
Table 5.2-24 Maximum Hourly and Annual Emergency Diesel Generator Emissions 5.2-50
Table 5.2-25 Maximum Hourly and Annual Emergency Diesel Fire-water Pump Emissions 5.2-51
Table 5.2-26 Maximum Hourly and Annual Cooling Tower PM10 Emissions 5.2-51
Table 5.2-27 Total Annual Potential Emissions, Normal Operation 5.2-52
Table 5.2-28 Summary of GHG Emissions 5.2-53
Table 5.2-29 Maximum Yearly Monitored Background Concentrations 2005-2007 ..... 5.2-54
Table 5.2-30 NAAQS/CAAQS Analysis for Project Construction 5.2-57
Table 5.2-31 Combustion Turbine Commissioning Modeling Stack and Emissions Data 5.2-57
Table 5.2-32 Maximum Modeled Concentrations for Project Combustion Turbine Commissioning 5.2-58
Table 5.2-33 Ambient Air Quality Impact Criteria (µg/m3) 5.2-59
Table 5.2-34 Stack Parameters and Emissions Data for the Combustion Turbines 5.2-60
Table 5.2-35 Stack Parameters and Emissions Data for the Ancillary Equipment 5.2-61
Table 5.2-36 Summary of GEP Analysis 5.2-62
Table 5.2-37 Maximum Modeled Concentrations for PHPP Normal Operations 5.2-63
Table 5.2-38 Stack Parameters and Emissions Data for the Combustion Turbines Start-up/Shutdown Modeling 5.2-64
Table 5.2-39 Maximum Modeled Concentrations for Project Startup/Shutdown Operations 5.2-64
Table 5.2-40 Class I Area PM10, PM2.5, and NO2 PSD Increment CALPUFF Modeling Result 5.2-66
Table 5.2-41 Class I Area Regional Haze CALPUFF Modeling Results 5.2-66
Table 5.2-42 Class I Area Nitrogen Deposition CALPUFF Modeling Results 5.2-67
Table 5.2-43 Dispersion Condition Frequency Analysis – Sector 303.75º – 326.25º 5.2-69
Table 5.2-44 Dispersion Condition Frequency Analysis – Sector 326.25º – 348.75º 5.2-70
Table 5.2-45 Dispersion Condition Frequency Analysis – Sector 348.75º – 11.25º 5.2-71
Table 5.2-46 VISCREEN Model Results 5.2-72
Table 5.2-47 Soils and Vegetation Analysis 5.2-73
Table 5.2-48 NAAQS/CAAQS Cumulative Modeling Results for Project Normal Operations 5.2-75

5.3 Biological Resource

Table 5.3-1 LORS Applicable to Biological Resources 5.3-1
Table 5.3-2 Agencies and Agency Contacts 5.3-7

Table 5.3-3 Required Biological Resource Permits and Permitting Schedule 5.3-7
Table 5.3-4 Potential Jurisdictional Status of Ephemeral Drainages and Perennial Waterways Found within 250 Feet of PHPP Transmission Line Corridor 5.3-12
Table 5.3-5 Special-status Species Occurring or Potentially Occurring in the Project Vicinity 5.3-29
Table 5.3-6 Direct Permanent Surface Disturbance Acreage* per Affected Habitat Community 5.3-39

5.4 Cultural Resources

Table 5.4-1 LORS Applicable to Cultural Resources 5.4-1
Table 5.4-2 Agency Contacts 5.4-7
Table 5.4-3 Summary of Cultural Resource Survey Activities 5.4-23
Table 5.4-4 Sites Recorded in Current PHPP Archaeological Survey Area 5.4-24
Table 5.4-5 Isolates Recorded in PHPP Survey Area 5.4-26
Table 5.4-6 Summary of Distribution of Archaeological Resources 5.4-27
Table 5.4-7 Historic Standing Structures Identified during Architectural “Windshield” Survey 5.4-31

5.5 Geologic Hazards and Resources

Table 5.5-1 LORS Applicable to Geological Resources and Hazards 5.5-1
Table 5.5-2 Agencies and Agency Contacts 5.5-2
Table 5.5-3 Significant Faults in Project Region 5.5-4
Table 5.5-4 Significant Earthquakes (M > 5.5) Near Project Vicinity 5.5-4
Table 5.5-5 MRDS Mineral Deposits in the Project Region 5.5-7

5.6 Hazardous Material Handling

Table 5.6-1 Summary of Applicable Hazardous Materials LORS 5.6-1
Table 5.6-2 Agencies and Agency Contacts 5.6-8
Table 5.6-3 Summary of Special Handling Precautions for Large Quantity Hazardous Materials 5.6-13
Table 5.6-4 Ammonia Release Scenario Results 5.6-26

5.7 Land Use

Table 5.7-1 LORS Applicable to Land Use 5.7-1
Table 5.7-2a City of Palmdale General Plan Land Use Designations Description 5.7-5
Table 5.7-2b City of Palmdale General Plan Land Use Designations Along Project Linear Facilities 5.7-6
Table 5.7-2c City of Palmdale Business Park Center Specific Plan Land Use Designations 5.7-8
Table 5.7-3a City of Palmdale Zoning Within and Near PHPP Plant Site 5.7-10
Table 5.7-3b City of Palmdale Zoning Designations Along Project Linear Facilities 5.7-11
Table 5.7-4 City of Lancaster General Plan Land Use Designations 5.7-12
Table 5.7-5 Lancaster Zoning Designations Near PHPP Plant Site 5.7-13

Table 5.7-6 Antelope Valley Areawide General Plan Land Use Designations 5.7-14
Table 5.7-7 Los Angeles County Zoning Ordinance Description 5.7-15
Table 5.7-8 Agency Contact List 5.7-16
Table 5.7-9 Land Use Related Permits Required and Schedule 5.7-17
Table 5.7-10 Farmland of Importance within the Project Area 5.7-21

5.8 Noise

Table 5.8-1 LORS Applicable to Noise 5.8-1
Table 5.8-2 City of Palmdale Maximum Acceptable Levels 5.8-3
Table 5.8-3 City of Lancaster Noise Compatible Land Use Objectives 5.8-4
Table 5.8-4 Agencies and Agency Contacts 5.8-4
Table 5.8-5 Definition of Technical Terms Related to Noise 5.8-6
Table 5.8-6 Ambient Noise Measurement Locations 5.8-8
Table 5.8-7 Ambient Noise Measurements – May 29, 2007 to May 30, 2007 ..... 5.8-9
Table 5.8-8 Average Ambient Noise Levels Measured During Four Quietest Nighttime Hours 5.8-10
Table 5.8-9 Average Ambient Noise Levels Measured During Normal Daytime Working Hours 5.8-10
Table 5.8-10 Construction Equipment Noise Emissions 5.8-11
Table 5.8-11 PHPP Construction Equipment 5.8-12
Table 5.8-12 Construction Noise Levels for Residential Structures 5.8-13
Table 5.8-13 PHPP Equipment Noise Emissions 5.8-15
Table 5.8-14 PHPP Operation Phase Noise Levels at Nearest Residential Structures 5.8-16

5.9 Paleontological Resources

Table 5.9-1 Summary of LORS for Paleontological Resources 5.9-1
Table 5.9-2 Agencies and Agency Contacts 5.9-3
Table 5.9-3 Geologic Units Underlying the PHPP Project and their Paleontological Sensitivity Ratings 5.9-7

5.10 Public Health

Table 5.10-1 Summary of LORS Applicable to Public Health 5.10-2
Table 5.10-2 Administering Agency and Contact Information 5.10-7
Table 5.10-3 TAC Potentially Emitted from the PHPP 5.10-9
Table 5.10-4 Risk Assessment Health Values for TAC of Concern 5.10-12
Table 5.10-5 TAC Emissions for Turbines/Duct Burners with SCR and Oxidation Catalyst 5.10-14
Table 5.10-6 TAC Emissions for Cooling Tower 5.10-15
Table 5.10-7 TAC Emissions for Auxiliary Boiler and HTF Heater 5.10-16
Table 5.10-8 TAC Emissions for Emergency Internal Combustion Engines 5.10-17
Table 5.10-9 Summary of Maximum Impacts 5.10-21

Table 5.10-10 Summary of Cancer Risk at the MEIR by Source and Pathway 5.10-22
Table 5.10-11 Summary of Cancer Risk at the MEIR by Toxic Contaminant and Pathway 5.10-22

5.11 Socioeconomics

Table 5.11-1 LORS Applicable to Socioeconomics 5.11-1
Table 5.11-2 Population Estimates and Projection 5.11-4
Table 5.11-3 Average Annual Population Growth Rates 5.11-6
Table 5.11-4 2006 Employment by Industry for Los Angeles, San Bernardino and Kern Counties 5.11-7
Table 5.11-5 Employment by Industry (Year 2006 Annual Average) 5.11-9
Table 5.11-6 Hospitals Serving the Project Area 5.11-11
Table 5.11-7 Summary of Schools and Enrollment in Palmdale School District 5.11-12
Table 5.11-8 Summary of School Enrollment in Westside Union School District 5.11-14
Table 5.11-9 Summary of School Enrollment in Antelope Valley Union High School District 5.11-15
Table 5.11-10 County of Los Angeles Expenses and Revenues for FY 2006-2007 ..... 5.11-16
Table 5.11-11 City of Palmdale Expenses and Revenues for FY 2006-2007 ..... 5.11-17
Table 5.11-12 PHPP Construction Workforce by Skill 5.11-19
Table 5.11-13 Available Labor: Long Beach Metropolitan Statistical Area (Los Angeles County) 5.11-21
Table 5.11-14 Available Labor: Kern County Statistical Area 5.11-23
Table 5.11-15 Available Labor: Ontario Metropolitan Statistical Area 5.11-25
Table 5.11-16 Available Construction Labor by Skill 5.11-27
Table 5.11-17 Environmental Justice Characteristics 5.11-33

5.12 Soils

Table 5.12-1 LORS Applicable to Soils 5.12-1
Table 5.12-2 Permits Required and Permit Schedule 5.12-3

5.13 Traffic and Transportation

Table 5.13-1 Traffic and Transportation LORS Summary 5.13-1
Table 5.13-2 Agencies and Agency Contacts 5.13-4
Table 5.13-3 Required Permits and Permit Schedule 5.13-5
Table 5.13-4 Level of Service Description for Intersections 5.13-7
Table 5.13-5 Intersection Peak Hour Levels of Service (Without the Proposed PHPP) 5.13-8
Table 5.13-6 Existing and 2011 Baseline 24-Hour Roadway Traffic Volumes, Approximate Design Capacities, and Truck Volumes 5.13-9
Table 5.13-7 Year 2011 Intersection Peak Hour Levels of Service With Average and Peak Construction Traffic 5.13-13
Table 5.13-8 2011 Baseline 24-Hour Roadway Traffic Volumes, Project Construction Traffic Volumes and Project Operations Traffic Volumes 5.13-15

Table 5.13-9 HRSG Stack Location and Elevation 5.13-17
Table 5.13-10 Turbine Data Required for Vapor Plume Analysis 5.13-18
Table 5.13-11 Turbine Stack Vapor Plume Modeling Results 5.13-18
Table 5.13-12 Tower Performance Data Input to SACTI 5.13-20
Table 5.13-13 Cooling Tower Elevated Plume Modeling Results 5.13-21

5.14 Transmission Line Safety and Nuisance

Table 5.14-1 Transmission Line Design and Construction LORS 5.14-1
Table 5.14-2 Electric and Magnetic Field LORS 5.14-2
Table 5.14-3 Hazardous Shock LORS 5.14-3
Table 5.14-4 Communications Interference LORS 5.14-3
Table 5.14-5 Fire Hazard LORS 5.14-4
Table 5.14-6 Involved Agencies 5.14-4
Table 5.14-7 EMF Study Conductor Information 5.14-6

5.15 Visual Resources

Table 5.15-1 Summary of Applicable Visual Resources LORS 5.15-1
Table 5.15-2 Agencies and Agency Contacts 5.15-3
Table 5.15-3 Equipment Dimensions 5.15-10
Table 5.15-4 HRSG and Cooling Tower Visible Plume Modeling Results 5.15-14

5.16 Waste Management

Table 5.16-1 LORS Applicable to Waste Management 5.16-1
Table 5.16-2 Agencies and Agency Contacts 5.16-7
Table 5.16-3 Permits Required and Permit Schedule 5.16-7
Table 5.16-4 Solid and Hazardous Waste Disposal Facilities 5.16-8
Table 5.16-5 Summary of Construction Waste Streams and Management Methods 5.16-12
Table 5.16-6 Summary of Operation Waste Streams and Management Methods 5.16-13

5.17 Water Resources

Table 5.17-1 LORS Applicable to Water Resources 5.17-1
Table 5.17-2 Water Resources Agencies and Contact Information 5.17-7
Table 5.17-3 Required Water Resources Permits and Schedule 5.17-7

5.18 Worker Safety

Table 5.18-1 Worker Safety LORS Summary 5.18-1
Table 5.18-2 Potentially Applicable Topics Addressed in Title 8 CCR 5.18-4
Table 5.18-3 Fire Protection Association Fire and Explosion Hazards Standards 5.18-7
Table 5.18-4 Agencies and Agency Contacts 5.18-8
Table 5.18-5 Permits and Approvals 5.18-8

Table 5.18-6 Project Hazard Analysis (Construction and Operations Phases) 5.18-10
Table 5.18-7 Basic Protective Equipment Guide 5.18-14
Table 5.18-8 Training Programs and Target Employees (Construction and Operation Phases) 5.18-15

List of Figures

1.0 Executive Summary

Figure 1-1 Regional and Vicinity Map 1-9
Figure 1-2 Project Site and Surrounding Area 1-10

2.0 Project Description

Figure 2-1 Project Site (Plant Site and Linear Facilities) 2-35
Figure 2-2 Plant Site Photographs – Existing Conditions 2-49
Figure 2-3a Plant Site without Simulated Project Facilities 2-50
Figure 2-3b Plant Site with Simulated Project Facilities 2-51
Figure 2-4 General Arrangement Site Plan 2-52
Figure 2-5 General Arrangement Power Block 2-53
Figure 2-6 Elevation Drawings (two views on same page as one graphic) 2-54
Figure 2-7a Heat Balance – Base Load 2-55
Figure 2-7b Heat Balance – Peak Load 2-56
Figure 2-7c Heat Balance – Peak Load with Full Solar 2-57
Figure 2-8 Photo of Solar Array Field 2-58
Figure 2-9 Aerial Photo of Kramer Junction SEGS Site 2-59
Figure 2-10 Plant One Line Electrical Diagram 2-60
Figure 2-11a Water Balance – Base Load 2-61
Figure 2-11b Water Balance – Peak Load 2-62
Figure 2-11c Water Balance – Peak Load with Full Solar 2-63
Figure 2-12a Transmission Line Segment 1 – Existing Conditions 2-64
Figure 2-12b Transmission Line Route Segment 1 – With Simulated PHPP Facilities 2-65
Figure 2-13b Transmission Line Segment 2 – Existing Condition 2-66
Figure 2-13b Transmission Line Segment 2 – With Simulated PHPP Facilities 2-67

4.0 Project Alternatives

Figure 4-1 Project Alternatives 4-16

5.2 Air Quality

Figure 5.2-1 Annual Wind Rose – Palmdale 5.2-85
Figure 5.2-2 Elevation Contours Within 10-Miles of the Project 5.2-86
Figure 5.2-3 Buildings and Sources Used in GEP Analysis 5.2-87
Figure 5.2-4 Location of Sources and Facilities Included in Cumulative Modeling 5.2-88
Figure 5.2-5 Location of PSD Class I Areas Relative to the PPHP 5.2-89
Figure 5.2-6 22.5º Wind Direction Sectors Encompassing San Gabriel Wilderness Area 5.2-90

5.3 Biological Resources

Figure 5.3-1 Biological Survey Area 5.3-59
Figure 5.3-2 Project Site and Burrowing Owl Habitat 5.3-60
Figure 5.3-3 Project Site and Potential Jurisdictional Waters 5.3-61
Figure 5.3-4 Project Site and Habitat Communities 5.3-62
Figure 5.3-5 Project Site and California natural Diversity Database Area 5.3-63
Figure 5.3-6 Project Site and Special -Status Species/Sign Observed 5.3-64
Figure 5.3-7 Project Site and Los Angeles County Designated Significant Ecological Areas 5.3-65

5.4 Cultural Resources

Figure 5.4-1 Archaeological Sensitivity Zones Developed in the City of Palmdale General Plan 5.4-44
Figure 5.4-2 Traditional Ethnographic Territories within the Project Area 5.4-45

5.5 Geologic Hazards and Resources

Figure 5.5-1 Geology Map 5.5-13
Figure 5.5-2 Alquist-Priolo Fault Zones in the Vicinity of the Project Site and Linears 5.5-14
Figure 5.5-3 Alquist-Priolo Fault Zones in the Project Region 5.5-15
Figure 5.5-4 Liquefaction Zones in the Vicinity of the Project Site and Linears 5.5-16
Figure 5.5-5 Mineral Resources in the Vicinity of the Project Site and Linears 5.5-17

5.7 Land Use

Figure 5.7-1 Land Use Study Area 5.7-25
Figure 5.7-2a City of Palmdale General Plan Land Use Designations 5.7-26
Figure 5.7-2b City of Lancaster General Plan Land Use Designations 5.7-27
Figure 5.7-2c County of Los Angeles General Plan Land Use Designations 5.7-28
Figure 5.7-3a City of Palmdale Zoning 5.7-29
Figure 5.7-3b City of Lancaster Zoning 5.7-30
Figure 5.7-3c County of Los Angeles Zoning 5.7-31
Figure 5.7-4 Air Installation Compatible Use Zone 5.7-32
Figure 5.7-5 Important Farmland in the Vicinity of the Project Area 5.7-33

5.8 Noise

Figure 5.8-1 CNEL Noise Contours – Air Force Plant 42/Palmdale Regional Airport 5.8-19
Figure 5.8-2 Ambient Noise Measurement Locations 5.8-20
Figure 5.8-3 Leq(1) Noise Contours – PHPP Operation 5.8-21
Figure 5.8-4 CNEL Noise Contours – PHPP Operation 5.8-22

5.9 Paleontological Resources

Figure 5.9-1 Locations of Paleontologically Sensitive Geologic Units Underlying the PHPP Plant Site and Linear Facilities 5.9-17

5.10 Public Health

Figure 5.10-1 Population Density within Three-miles of the Plant Site 5.10-28
Figure 5.10-2 Residential, Worker and Sensitive Receptors within Three-miles of the Plant Site 5.10-29

5.11 Socioeconomics

Figure 5.11-1 Regional Economic Setting 5.11-36
Figure 5.11-2 Percent Minority by Census Block Group 5.11-37
Figure 5.11-3 Proportion Below Poverty Level by Census Block Group 5.11-38

5.12 Soils

Figure 5.12-1 Soils Mapsheets (14) 5.12-12

5.13 Traffic and Transportation

Figure 5.13 1 Regional Transportation Access 5.13-25
Figure 5.13 2 Local Transportation Access 5.13-26
Figure 5.13 3 Peak Month Project Construction Traffic 5.13-27
Figure 5.13 4 Project Operations Related Traffic 5.13-28

5.14 Transmission Line Safety and Nuisance

Figure 5.14-1 Typical ROW East of Powerplant (After Project) 5.14-9
Figure 5.14-2 Typical ROW View 1, West of Pearblossom Looking West (Before Project) 5.14-10
Figure 5.14-3 Typical ROW View 1, West of Pearblossom Looking West (After Project) 5.14-11
Figure 5.14-4 Typical ROW View 2, West of Pearblossom Looking West (Before Project) 5.14-12
Figure 5.14-5 Typical ROW View 2, West of Pearblossom Looking West (After Project) 5.14-13
Figure 5.14-6 Typical ROW View 1, West of Pearblossom, Looking West 5.14-14
Figure 5.14-7 Typical ROW View 2, West of Pearblossom, Looking West 5.14-15

5.15 Visual Resources

Figure 5.15-1 Regional Visibility of the Project Site 5.15-1
Figure 5.15-2 Local Visibility of the Transmission Line Route 5.15-2
Figure 5.15-3 Project Site and Key Observation Points 5.15-3
Figure 5.15-4a View from KOP-1 Looking Southwest Toward PHPP Site – Existing Condition 5.15-4
Figure 5.15-4b View from KOP-1 Looking Southwest Toward PHPP Site – Simulated Condition 5.15-5
Figure 5.15-5a View from KOP-2 Looking East Toward PHPP Site – Existing Condition 5.15-6
Figure 5.15-5b View from KOP-2 Looking East Toward PHPP Site – Simulated Condition 5.15-7

Figure 5.15-6a View from KOP-3 Looking Northeast Toward PHPP Site – Existing Condition.....5.15-8
Figure 5.15-6b View from KOP-3 Looking East Toward PHPP Site – Simulated Condition.....5.15-9
Figure 5.15-7a View from KOP-4 Looking South Toward the Transmission Line Route – Existing Condition 5.15-10
Figure 5.15-7b View from KOP-4 Looking South Toward the Transmission Line Route – Simulated Condition.....5.15-11
Figure 5.15-8a View from KOP-5 Looking North Toward the Transmission Line Route – Existing Condition 5.15-12
Figure 5.15-8b View from KOP-5 Looking North Toward the Transmission Line Route – Simulated Condition.....5.15-13
Figure 5.15-9a View from KOP-6 Looking West Toward the Transmission Line Route – Existing Condition 5.15-14
Figure 5.15-9b View from KOP-6 Looking West Toward the Transmission Line Route – Simulated Condition.....5.15-15

5.17 Water Resources

Figure 5.17-1 Local Water Resources.....5.17-16